BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Name of Work: Community Property and Park Maintenance in Ward No 14 Bagalagunte, Dasarahalli Sub Division

Job Code:014-19-000043 | Est. Cost Rs 2.50 Lakhs

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRB 2-1.2: Earthwork in surface excavation in hard soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (A) / 2.3.1 (P.5/I.2.2 PW, P & IWTD -SR 2016-17)								
		Cum	19	2.50	1.00	0.20	10.00		
	Basic Rate	220.00							
	Add Area Weightage 6%	13.20					10.00	233.20	2332.00
	Total	233.20							
2	KSRB 4.1-2 : Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarseaggregates @ 0.892 cum and fine aggregtes @ 0.465 cum machine mixed, concrete laid in laye` not exceeding 15 cms. Thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.2) PWD - SR 2016-17)								
	Long wall	Cum	19	2.50	1.00	0.15	7.13		
	Basic Rate	5046.00							
	Add Area Weightage 6%	302.76					7.13	5348.76	38110.00
	Total	5348.76							
3	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarseaggregates @ 0.64 cum and fine aggregtes @ 0.43 cum,with superlastiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in laye` not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2, (Page No. 12, IT. No. 4.5) PWD SR 2016-17								
		Cum	19	2.50	1.00	0.15	7.13		
							7.13	5874.52	41856.00

Scanned with CamScanner

	Basic Rate	5542.00							
	Add Area Weightage 6%	332.52							
	Total	5874.52							
4	Providing and fixing Granite benches including cost of Materials labour as per Specification (Data Rate Approved)								
		Nos	19				19.00	8000.00	152000.00
5	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Page No. 133 Item No. 17.1 PWD SR 2016-17								
		Cum	Qty Vide Item No. 1				10.00	73.99	740.00
	Loading and Unloading Charges	57.00							
	Lead 4 KMs 2x1.28x4	12.80							
		69.80							
	Add Area Weightage 6%	4.19							
	Total	73.99							
							Sub Total		235038.00
									11752.00
6	Trender primium Charge 5%								3210.00
7	Miscellaneous and UnforessenCharges							Total	250000.00

Rupees Two Lakhs Fifty thousand Only

Assistant Engineer
Ward No 14

Assistant Executive Engineer
T. Dasarahalli Sub-Division

Executive Engineer
Dasarahalli Division

ಸಂ. EE/DD/AS/ವಿ/18-19 ದಿನಾಂಕ : 17.01.19

ರೂ. 250000/ (Two lakh Fifty thousand only)

ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ದಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ಸಂ. EE/DD/TS/ 37/18-19 ದಿನಾಂಕ : 17.01.19

ರೂ. ₹250000/-(Two lakh fifty thousand only)

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ದಿ.ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

Scanned with CamScanner